



ALL CORRESPONDENCE TO BE ADDRESSED TO THE GENERAL MANAGER

Central Electricity Board

CORPORATE OFFICE

P.O. BOX 134 | Rue du Savoir | Cybercity, Ebène 72201

MAURITIUS

TEL No. : (230) 404 2000
TELEFAX No. : (230) 454 7630 / 7632
E-MAIL : ceb@intnet.mu
WEBSITE : ceb.mu
VAT Reg. No. : VAT22000591
BRN : F07000041

OUR REF: **CPB/30/2023 – Add. 4**

YOUR REF:

12 January 2024

Attention: All Bidders

Dear Sir/Madam,

CPB/30/2023 - Design, Supply, Installation, Testing and Commissioning of Ten 66/22 kV GIS Substations for the Republic of Mauritius

Addendum No. 4

Bidders are hereby informed of the following additions to the Employer's Requirements for **Rose Belle Substation**.

- **Section 7.4.1 Earthworks/Enabling Works**

The following is added after the end of the first sentence:

The Contractor shall implement a cut-off swale along the boundary of the subject site to intercept overland flows and same shall be discharged into the existing major drainage path/watercourse, as per drawing CEB-GIS-20-39 Rev 1. The dimensions of the cut off swale shall be minimum: bottom width 0.5m, top width 1.5m, and 1 m deep.

Any additional stormwater generated by the proposed development shall be contained therein.

The area of development shall not be tarred or rendered impermeable to allow percolation of the surface runoff. The Contractor shall propose a road surface suitable for movement of heavy vehicles carrying the heaviest equipment of the site.

The floor level of the proposed development shall be raised to a minimum of 500 mm above road level (Coriolis Road) to prevent ingress of water.

- **Section 7.4.2 Drainage**

The following is added after the end of the first sentence:

A detailed Stormwater Drainage Report duly signed by a Registered Professional Engineer in Mauritius stating the impact of the proposed development shall be submitted by the Contactor during the detail design stage.

Yours faithfully,

J. Lam
Ag. Head of Supply Chain